



**Dalton Whitfield Joint Development Authority
S. Hamilton Street Residential Infill**

1/10/2025

ITEM No.	DESCRIPTION	ESTIMATED QUANTITY	UNIT OF MEASURE	UNIT PRICE	TOTAL PRICE
SITE PREPERATION					
1.	Clearing, Demolition & Grubbing	1	LS		
2.	Mobilization and Demobilization	1	LS		
3.	Grading Complete	1	LS		
4.	Import Structural Fill	2,500	CY		
STREET IMPROVEMENTS					
5.	1.5" (165 lb/sy) Recycled Asphalt Concrete 9.5 mm Superpave	222.0	Tons		
6.	2" (220 lb/sy) Recycled Asphalt Concrete 19 mm Superpave	296.0	Tons		
7.	Bituminous Tack Coat (.07 gal/sy)	188	GAL		
8.	Bituminous Prime Coat (0.25 gal/sy)	672	GAL		
9.	8" Graded Aggregate Base Course	2,684	SY		
10.	6" Graded Aggregate Base Course	264	SY		
11.	4" Graded Aggregate Base Course	2,735	SY		
12.	8" Reinforced Header Curb	1,852	LF		
13.	24" Wide Concrete Curb & Gutter	850	LF		
14.	30" Rollover Curb and Gutter	225	LF		
14.	Concrete Paving (4" Thick)	2,750	SY		
15.	Concrete Paving (6" Thick)	270	SY		
16.	Gravel Section (6" Thick)	765	SY		
17.	Curb Cut Wheelchair Ramp (ADA)	20	EA		
18.	Bollard (Removable)	1	EA		
19.	Bollard	1	EA		
20.	5" Wide Paint (Solid Stripe for Parking Lines)	135	LF		
21.	8" Wide Solid White Crosswalk Stripe (Thermoplastic)	1	LS		
22.	24" Wide Solid White Stop Bar Stripe (Thermoplastic)	140	LF		
23.	Solid White Directional Arrow (Thermoplastic)	20	EA		
24.	Parking/Roadway Signage	1	LS		
STORM SEWER SYSTEM					
25.	Storm Drain Pipe, RCP				
A.	18-inch	555	LF		
B.	24-inch	62	LF		
C.	30-inch	29	LF		
26.	12" Storm Drain Pipe, HDPE	506	LF		
27.	4'x4' Junction Box/Inlet	10	EA		
28.	Single Wing Catch Basin	4	EA		
29.	Double Wing Catch Basin	4	EA		
30.	Precast Drop Inlet, Type A (W/Grate Top)	4	EA		
31.	Precast Drop Inlet, Type E	1	EA		
32.	Underground Detention System Complete	1	LS		
33.	Outlet Control Structure	1	EA		
SANITARY SEWER AND WATER UTILITIES					
34.	4" DIP Sanitary Sewer Lateral (Fittings, Caps Included)	440	LF		
35.	Connect Sewer Lateral Pipe to Exist. Sewer Main	2	EA		
36.	Sanitary Sewer Manhole	10	EA		
37.	Sanitary Sewer Dog House Manhole	2	LF		
38.	Sanitary Clean Out	40	EA		
39.	8" DIP Sanitary Sewer Line (taps, fittings, valves included)	1,000	LF		
39.	16"x8" Tapping Saddle and Valve	3	EA		
40.	12"x8" Tapping Saddle and Valve	1	EA		
41.	Fire Hydrant Assembly	4	EA		
42.	8" DIP Water Line (taps, fittings, valves included)	1,300	LF		
43.	2" SCH 40 PVC Water Line (taps, fittings, valves included)	105	LF		
44.	Water Meter, 3/4"	40	EA		
MISCELLANEOUS					
45.	Erosion Control/BMPs (All Items As Shown On Plans)	1	LS		
46.	Storm Water Sampling for NPDES Permit	1	LS		
47.	Monitoring, NOI, NOT, Record Keeping & Reporting NPDES to GA EPD	1	LS		
48.	Materials Testing	1	LS		
49.	Cash Allowance (Authorized by Owner & Engineer)	1	LS		

TOTAL AMOUNT BASE BID

(In Figures)

(In Words)

ALTERNATE BID 1

Item No.	DESCRIPTION	ESTIMATED QUANTITY	UNIT OF MEASURE	UNIT PRICE	TOTAL PRICE
STREET IMPROVEMENTS					
1.	Irrigation System Complete	1	LS		

TOTAL AMOUNT ALTERNATE BID No. 1

(In Figures)